

Formular F3

OBIECTIV: ISC1 AMENAJ. PCT.INTERNAT.FRONTIERA

LISTA

cu cantitatile de lucrari pe categorii de lucrari

Obiect: ISC1 PUNCTE ACOSTARE

Categorie: ISC24 EX.ANCASTR.APE MICI INCL.RAMPA

[ron]

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	
1	TSA02C1	82 M CUB	5,00000		
	SAP.MAN.IN SPATII LIMIT.SUB 1M CU TALUZ VERT.NESPR .IN PAM.NECOEZ.SI SL.COEZ.ADINC.<0,75M T.TARE				
2	TSD06B1	82 SUTE MC	0,08000		
	COMPACTARE CU PLACA VIBRAT.DE 1,6T UMPLUTURA PAMIN T NECOEZIN IN STRAT DE 20-30CM				
3		2100910 M CUB	2,90000		
	BETON MARFA CLASA C10/8 (BC10/B150)				
4	CA01J1	82 M CUB	2,90000		
	TURNARE BETON SIMPLU IN STRATURI DE 5-20CM PT.EGAL IZARI LA CONSTRUCTII EDILITARE (APEDUCTE, CANALE)				
5	CZ0301E1	82 KG	610,00000		
	CONFECT.ARMAT.FASONARE BARE PT.FUNDATII IZOL.CONTI NUI SI RADIERE IN ATEL.CENT.PC 52 D=10- 16 MM \$				
6	PD01A1	82 KG	610,00000		
	MONT.ARMATURI PT.BETON ARMAT IN FUND.RADIERE ELEV. INFRASTR.SUPRASTR.POD GRINZI DREPTE,CADRE ETC.				
7	PC02A1	82 MP	50,00000		
	COFRAJE PT.BETON ELEVATIE SI ZIDURI SPRIJ.DIN PANO URI CU PLACAJ P CU SUPRAFETE PLANE				

Nr. Crt.	Capitol lucrari Simbol Denumire resursa Observatii Corectii Liste Anexe	U/M	Cantitatea	Pretul unitar a)materiale b)manopera c)utilaj d)transport Total(a+b+c+d)	Valoare
8	TRA02A35	82	TONE		0,76000
	TRANSPORTUL RUTIER AL MATERIALELOR, SEMIFABRICATELO R CU AUTOCAMIONUL PE DIST.= 35 KM. \$				
9		2100916	M CUB		21,40000
	BETON MARFA CLASA C30/25 (BC30/B400)				
10	TRA06A05	82	TONE		61,00000
	TRANSPORTUL RUTIER AL BETONULUI-MORTARULUI CU AUTO BETONIERA DE 5,5MC DIST. =5 KM \$				
11	PB09B1	82	M CUB		21,40000
	TURN.BET.ARMAT B150 IN FUND.TALPI RADIERE POMPA				
12	H1B02A5	82	MP		7,40000
	PREGATIREA SUPRAF.ROSTURI.LUCRU PT.BETONARE, LA ROS T.ORIZ.PRIN BUCIARD.MAN.+SUFL.AER+JET APA				
13	TSC04G1	82	SUTE MC		0,07000
	SAP.MEC.CU EXC.DE 0,71-1,25MC IN PAM.CU UMID. NAT. DESC.AUT.(MAT.UEMPL. INCL 30% SPOR SELECTARE)				
14	TRA01A01	82	TONE		98,00000
	TRANSPORTUL RUTIER AL MATERIALELOR, SEMIFABRICATELO R CU AUTOBASCULANTA PE DIST.= 1 KM. \$				
15	TSD17A1	82	M CUB		54,00000
	UMPLUT.COMPACTATE LA PROFIL.TALUZ.PE 0,5M GROS.EXE CUT.MAN.ODATA CU EXEC.MEC.A RAMBL.PAM.NECOEZ.				
16	DA06B1	82	M CUB		63,00000
	STRAT AGREG NAT CILINDRATE CU FUNC REZIST FILTRANT IZOLAT AERISIRE SI ANTICAP CU ASTER MEC BALAST				

Nr. Crt.	Capitol lucrari Simbol Denumire resursa Observatii Corectii Liste Anexe	U/M	Cantitatea	Pretul unitar a)materiale b)manopera c)utilaj d)transport Total(a+b+c+d)	Valoare
17	TRA06A05	82	TONE		139,00000
	TRANSPORTUL RUTIER AL BETONULUI-MORTARULUI CU AUTO BETONIERA DE 5,5MC DIST. =5 KM \$				
18	DA12B1	82	M CUB		93,10000
	STRAT FUND REPROF P SPARTA PT DRUM CU ASTERNERE MECANICA EXEC CU IMPANARE FARA INNOROIRE				
19	TRA01A08	82	TONE		199,00000
	TRANSPORTUL RUTIER AL MATERIALELOR CU AUTOBASCULAN TA PE DIST.= 8 KM. (PIATRA SPARTA)				
20	CZ0104A1	82	M CUB		7,10000
	PREPARARE BETON C8/10				
21	CA01J1	82	M CUB		7,10000
	TURNARE BETON SIMPLU IN STRATURI DE 5-20CM PT.EGAL IZARI LA CONSTRUCTII EDILITARE (APEDUCTE,CANALE)				
22	CZ0301K1	82	KG		1.554,00000
	CONFECT.ARMAT.FASONARE BARE PT.FUNDATII IZOL.CONTI NUI SI RADIERE IN ATEL.SANT.PC 52 D=10- 16 MM \$				
23	PC02A1	82	MP		158,00000
	COFRAJE PT.BETON ELEVATIE SI ZIDURI SPRIJ.DIN PANO URI CU PLACAJ P CU SUPRAFETE PLANE				
24	TRA02A35	82	TONE		2,03000
	TRANSPORTUL RUTIER AL MATERIALELOR, SEMIFABRICATELO R CU AUTOCAMIONUL PE DIST.= 35 KM. \$				
25	PD01A1	82	KG		1.554,00000
	MONT.ARMATURI PT.BETON ARMAT IN FUND.RADIERE ELEV. INFRASTR.SUPRASTR.POD GRINZI DREPTE,CADRE ETC.				

Nr. Crt.	Capitol lucrari Simbol Denumire resursa Observatii Corectii Liste Anexe	U/M	Cantitatea	Pretul unitar a)materiale b)manopera c)utilaj d)transport Total(a+b+c+d)	Valoare
26		2100916 M CUB		43,00000	
	BETON MARFA CLASA C30/25 (BC30/B400)				
27	PB10C1	82 M CUB		43,00000	
	TURN.BET.ARMAT IN ZIDURILE DE SPRIJIN				
28	TRA06A05	82 TONE		126,00000	
	TRANSPORTUL RUTIER AL BETONULUI-MORTARULUI CU AUTO BETONIERA DE 5,5MC DIST. =5 KM		\$		
29	H1B02A5	82 MP		25,00000	
	PREGATIREA SUPRAF.ROSTURI.LUCRU PT.BETONARE, LA ROS T.ORIZ.PRIN BUCIARD.MAN.+SUFL.AER+JET APA				
30	CB18C1	82 MP		11,30000	
	REALIZARE ROST DE DILATATIE INTRE TRONS. ZIDULUI D E SPRIJIN DE 2CM GR.DIN POLIST. EXPANDAT (ASIMILAT)				
31	IFA09A1	82 M		50,00000	
	ETANSARE ROSTURI CU MASTIC ELASTIC NEBITUMINOS (AS IMILAT)				
32	TSD15A1	82 M CUB		2,70000	
	STRAT DE REPART.DIN NISIP SUB PRISMA DE BALASTARE CF COMPACTAT CU RULOU COMPRESOR DE 10-12T				
33	DA19A1	82 MP		133,00000	
	STRAT SEPARATOR FOLIE PVC (ASIM-FARA MAT.)				
34		8000382 MP		146,00000	
	FOLIE PVC PLASTIFIATA STRATIFICATA				

Nr. Crt.	Capitol lucrari Simbol Denumire resursa Observatii Corectii Liste Anexe	U/M	Cantitatea	Pretul unitar a)materiale b)manopera c)utilaj d)transport Total(a+b+c+d)	Valoare
35	DZ30A1	82	M CUB		31,00000
	PREP. BETON BCR 4.5				
36	CB01A1	82	MP		8,30000
	COFRAJE IN CUZINETI FUND PAHAR,FUND UTILAJE,DIN PA N REF,DIN SCINDURI RAS SC SI SUBSC INCL SPIJINIRI				
37	TRA02A05	82	TONE		78,00000
	TRANSPORTUL RUTIER AL MATERIALELOR, SEMIFABRICATELO R CU AUTOCAMIONUL PE DIST.= 5 KM. \$				
38	CA02C1	82	M CUB		31,00000
	TURNARE MANUALA A BET. LA IMBRACAMINTEA DRUMULUI				
39	TSC04G1	82	SUTE MC		1,20000
	SAP.MEC.CU EXC.DE 0,71-1,25MC IN PAM.CU UMIDITATE NATURAL DESC.AUT.TER.CAT.3				
40	TRA01A01P	82	TONE		160,00000
	TRANSPORTUL RUTIER AL PAMINTULUI SAU MOLOZULUI CU AUTOBASCULANTA DIST.= 1 KM \$				
41	TSD01C1	82	M CUB		89,00000
	IMPRASTIEREA CU LOPATA A PAMINT.AFINAT, STRAT UNIFO RM 10-30CM.GROS CU SFARIM.BULG.TEREN TARE				
42	TSD06B1	82	SUTE MC		0,09000
	COMPACTARE CU PLACA VIBRAT.DE 1,6T UMPLUTURA PAMIN T NECOEZIN IN STRAT DE 20-30CM				
43	DC04B1	82	M		28,00000
	TAIEREA CU MAS.CU DISC DIAMANT ROST CONTRACTIE SI DILATATIE BETON UZURA LA DRUMURI				

Nr. Crt.	Capitol lucrari Simbol Denumire resursa Observatii Corectii Liste Anexe	U/M	Cantitatea	Pretul unitar a)materiale b)manopera c)utilaj d)transport Total(a+b+c+d)	Valoare
44	IFA09A1	82 M		28,00000	
	COLMATAREA SI ETANSAREA ROSTURILOR CU MASTIC ELASTIC BITUMINOS (ASIM.)				
45	CL20C1	82 KG		3.430,00000	
	MONTAREA CONFECTIILOR METALICE APARENTE: DIVERSE EXCLUSIV PARAPETI, BALUSTRAZI, CHEPENGURI				
46	PK44C1	82 TONE		3,50000	
	CURATIREA DE RUGINA CU PERIA DE SIRMA A PIESELOR METALICE LA PARAPETE METALICE.				
47	PK48C1	82 TONE		7,00000	
	VOPSIREA PIESELOR MET CU UN STRAT DE VOPSEA MINIU SUP V351-3 CU PENSULA DE MINA LA PARAPETE				
48	PK49C1	82 TONE		3,50000	
	VOPSIREA PIESELOR MET CU DOUA STRAT. DE VOPSEA MINIU SUP V102-2A CU PENSULA DE MINA LA PARAPETE				
49	TSE03C1	82 SUTE MP		0,50000	
	FINISAREA MANUALA A TALUZURILOR, IN T.TARE				
50	TRA01A15	82 TONE		40,00000	
	TRANSPORTUL RUTIER AL MATERIALELOR CU AUTOBASCULAN TA PE DIST.= 15 KM. (PIATRABRUTA SI SPARTA)				
51	IFB07C1	82 MP		50,00000	
	PEREU ZIDIT GROSIME 30 CM DIN PIATRA BRUTA.				
52	IFB09D4	82 MP		50,00000	
	STRAT DRENANT CU GROSIMEA: 20 CM DIN PIATRA SPARTA ROCA SEDIMENTARA				

Nr. Crt.	Capitol lucrari Simbol Denumire resursa Observatii Corectii Liste Anexe	U/M	Cantitatea	Pretul unitar a)materiale b)manopera c)utilaj d)transport Total(a+b+c+d)	Valoare
53	CZ0204B1	82 M CUB		5,00000	
	PREPARARE MORTAR CIMENT PT ZID M100-Z CU CIM M30 I N INST CENTRALIZATE CU ADAOS DE VAR PASTA	\$			
54	TRA06A01	82 TONE		15,00000	
	TRANSPORTUL RUTIER AL BETONULUI-MORTARULUI CU AUTO BETONIERA DE 5,5MC DIST. =1 KM	\$			
55	TRA01A01	82 TONE		5,00000	
	TRANSPORTUL RUTIER AL MATERIALELOR CU AUTOBASCULAN TA PE DIST.= 1 KM. (NISIP)				
56	TSC35B2	82 SUTE MC		3,50000	
	EXC.TRA.INC.IN AUT.CU INC.FRONT.PE SENILE 1,0-2,50 MC.IN PAM.TER.CAT.2 LA DIST.<10M				
57	TRA01A01P	82 TONE		621,00000	
	TRANSPORTUL RUTIER AL PAMINTULUI SAU MOLOZULUI CU AUTOBASCULANTA DIST.= 1 KM	\$			
58	TSC19C1	82 SUTE MC		3,50000	
	SAPAT.CU BULDOZ.PE TRACT.81-180CP INCL.IMPING.PAMI NTULUI LA 10 M TEREN CAT.3				
59	DC03A1	82 BUCATA		56,00000	
	ANCORE OTEL BET CU LUNG BAR 1 M CU CIOC LA CAP PEN ANCOR DAL IMBR BET CIM VIBR LA ROST DE CONT LONG \$	\$			

INTOCMIT,